BRUHAT BANGALORE MAHANAGARA PALIKE

BBMP/2022-23/OW/WORK_INDENT51420

APPROVED SCHEDULE - B

No.EE/BTP/BBMP/E-PMT/01/2022-23, Date: 21-04-2022

Name of Work:Pot hole filling to Roads in Ward No.05 (Jakkur) Byatarayanapura Sub Division.(Additional).

Sl. No.	Approved Qty.	Description	Unit	Approved Tender Rates of Sambashiva ( )	
				In Figures	In Words
1	1282.55	Making up loss of of Material/irregulatities on shoulder ot the design level by adding fresh approved soil and compacting it with appropriate equipment complete as per specifications	Sqm	28.0	Rupees Twenty Eight Only
2	192.38	Providing, laying spreading and compacting graded stones aggregate to wet mix macadam specifications including premixing the material with water at OMC in mechanical mix plant carriage of mixed method of tipper to site, laying, in uniform layers with paver in sub base course on well prepared surface and compacting with vibratory roller to achieve the desired density complete as per specifications	Cum	1901.0	Rupees One Thousand Nine Hundred One Only
3	1282.55	Filling Pot-holes and Patch Repairs with Bituminous concrete, 40mm.KSRRB M3000-5. Removal of all failed material, trimming of completed excavation to provide firm vertical faces, cleaning of surface, painting of tack coat on the sides and base of excavation as per clause 500.0 back filling the pot hole with bituminous material as per clause 500.4 campacting traimming and finishing the surface to form a smooth continuous surface all as per clause 3004.2 complete as per specifications	Sqm	347.0	Rupees Three Hundred Forty Seven Only

Signature of the Contractor

Executive Engineer
Byarayanapura Division
BBMP, Bangalore - 92